


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CITIES SERVICE OIL CO.
Keesling No. 2

SEC. 1 T. 23 R. 10 W.
CNW SW
660' S. 660' E of W $\frac{1}{4}$ cor.

Total Depth. 3739
Comm. 7-10-42 Comp. 7-30-42
Shot or Treated. None
Contractor. Corbett-Barbour Drilling Co.
Issued. 9-26-42

County Reno.



CASING.

85/8" 160' cemented.
5 $\frac{1}{2}$ " 3727' cemented.

Elevation.

B.H.P. Gauge

Production. Pot. 3000B.

no wtr. (Ind. Cap.
4704 B.)

Figures Indicate Bottom of Formations.

sand	40
sand red bed & shale	162
shale and shells	190
red bed and shells	345
anhydrite	395
shale and shells	600
red bed	730
shale and red bed	1000
salt and shells	1250
shale and shells	1340
anhydrite	1355
anhydrite, shale & shells	1475
chalky lime	1500
broken lime	1709
sand	1731
broken lime	1773
lime and shale	1825
lime	1843
lime broken	1950
lime and shale	2165
shale & shells	2235
broken lime & shale	2368
lime and shale	2475
broken lime	2725
lime	3015
lime and shale	3295
lime broken	3365
lime	3605
chert	3612
shale and lime	3632
lime	3662
conglomerate	3700
shale and lime	3723
chat	3724
lime	3728
3728 Rot. T.D. = 3731 SLM	
lime	3739

Total Depth.

Corr. Top Viola 3724'
Penetration 15'

Loaded hole with 2500' water before
drilling in. Good show oil 3736-39
No fill up.