


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CITENS SERVICE OIL CO.
Keesling "B" No. 3.

SEC.1 T.23 R.10 W
SW NE SE
990'S 990'W E. cor.

Total Depth. 3748'
Comm. 11-22-42 Comp. 12-14-42
Shot or Treated. 500 Gals. 12-17-42
Contractor. Corbett-Barbour Drlg. Co.
Issued. 3-6-43

County. Reno



CASING:
10 3/4" 222' Cem.
7" 3724' Cem.

Elevation.

Production. Phy. Pot. 353 Oil
39 wtr

Figures Indicate Bottom of Formations.

sand	0-40
sand & red bed	222
red bed	350
shale & shells	1050
salt & shale	1260
shale & shells	1470
lime brkn	1660
lime	1705
sand	1735
lime	1790
lime brkn	1985
lime	2120
lime brkn	2245
lime & shale	2335
lime	2370
lime brkn & shale	2530
shale & shells	2635
shale	2651
lime	2690
shale & shells	2720
lime brkn & shale	2800
lime	2895
lime very hd	2970
lime	3080
shale & lime	3300
lime	3567
lime & chert	3596
shale	3614
chert	3619
lime	3621
cherty conglomerate	3661
shale	3700
conglomerate & lime	3725
3725 Rot. TD=3725 SIM	
lime	3748
Total Depth.	

Top Viola 3723
Penetration 25

Loaded hole w/2000' wtr before
drlg shoe. Good sh free oil
at 3748, no fillup