


N. APPLEMAN CO. ET AL  
 Grabor No. 1.

SEC.2 T.23 R. 10 W  
 SW NE NE

Total Depth. 3710'  
 Conn. 5-24-42 Comp. 6-21-42  
 Shot or Treated.  
 Contractor. Iron Drlg. Co.  
 Issued. 12-12-42

County. Reno



CASING:  
 8 5/8" 239'  
 5 1/2" 3688'

Elevation.

Production. Phy. Pot. 217 B.

Figures Indicate Bottom of Formations.

sand, red rock, shells	212
shale & shells	243
sand & shale	728
anhydrite	760
shale & shells	1372
shale	1387
brkn lime & sand	1475
lime gy	1510
sand & shale	1576
shale & sand	1743
lime & shale	1854
shale & lime	2034
shale & shells	2255
shale & lime strks	2356
lime & shale	2470
lime & shale brks	2510
shale & shells	2690
lime brkn & sand	2732
lime, cherty strks	2762
lime	2922
lime & shale brks	2952
shale & lime	3000
lime	3035
lime - shale brks	3077
lime	3085
shale & shells	3231
shale	3235
lime	3303
lime, shale brks	3364
lime	3380
lime & shale strks	3442
lime	3506
lime w/shale brks	3609
lime & shale	3657
shale & lime	3690
shale	3694
lime	3710
Total Depth.	

Tops:

Conglomerate	3617
Kinderhook	3624
Misener	3683
Upper Cryst. Viola	3687
Cherty Dolomitic Viola	3704
3700-10 saturation	