


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CITIES SERVICE OIL CO.
Hinshaw "A" No. 1.

SEC.2 T.23 R.10 W
CNW SE
660'S 660'E of Center

Total Depth. 3738'
Comm. 4-19-42 Comp. 5-23-42
Shot or Treated.
Contractor. Hisson Drig.Co.
Issued. 8-1-42

County. Reno



CASING:
8 5/8" 232' Cem.
5 1/2" 3713' Cem.

Elevation.

Production. BHP Gauge Pot.
1041 B., No Wtr

Figures Indicate Bottom of Formations.

surface sand	90	5-23-42 deepened
shale red	232	3733-38, no pay
shale red & shells	380	5-24-42 shot w/15 Qts.
brkn lime & shale	510	S.N.G. 3724-38
shale & lime	990	
shale & salt	1370	5- 9-42 500 Gals.Acid
sand & lime	1535	5-12-42 2000 Gals.Acid
lime & shale	1570	5-19-42 1000 Gals.Acid
lime	1600	5-29-42 4000 Gals.Acid
lime & shale	1745	
lime	1905	
lime & shale	2000	
lime	2040	
shale red	2052	
lime	2110	
shale & lime brkn	2290	
lime & shale	2325	
shale	2420	
shale & sdy lime	2487	
lime	2508	
lime brkn	2560	
lime & shale	2742	
lime	3000	
lime & shale	3085	
lime	3098	
shale	3143	
lime & shale	3158	
shale	3207	
lime	3322	
shale	3329	
lime	3340	
sand hrd	3351	
lime hrd	3387	
lime & shale brkn	3491	
lime & shalo	3557	
lime	3664	
shale & lime	3715	
lime & chert	3720	
3720 Rot.TD = 3715 SIM		
lime hrd	3725	
lime sft	3727	
lime hrd	3729	
lime	3733	
lime hrd	3738	
Total Depth.		

Corr. Top Viola 3711
Penetration 27

Loaded hole w/1200' wtr
before drlg in.
Pay 3723-29 no fillup

5-15-42 temp.pot.phy.
306 oil, no wtr 24 hrs
5-17-42 deepened 3729-33
Pay 3729-33 hole filled
from 1800' to 2700'
(900') in 1 1/2 hrs