


CITIES SERVICE OIL CO.
 Hinshaw "A" No.3.

SEC.2 T.23 R.10 W
 CNE SE
 660'S 660' W of E $\frac{1}{4}$ Cor.

County. Reno

Total Depth. 3745'
 Comm. 4-26-42 Comp. 5-16-42
 Shot or Treated. 500 Gals.5-20-42
 Contractor. Simpson & Noble, Inc.
 Issued. 7-25-42



CASING:
 8 5/8" 238' Cem.
 5 1/2" 3715' Cem.
 21' of 4" liner at 3730'

Elevation.

Production. Temp.Phy.Pot.
 206 BO,15BW

Figures Indicate Bottom of Formations.

surface clay & sand	160
red bed & sand shells	230
red bed & shells	370
red bed & shale	590
anhydrite	620
shale & lime shells	1058
shale & salt	1260
shale & lime shells	1430
lime	1628
lime brkn	1871
lime	2079
lime brkn & shale	2270
shale & shells	2390
lime & shells	2492
shale & lime shells	2672
shale & shells	2800
lime	2865
lime brkn	3085
shale & brkn lime	3190
lime brkn	3252
lime	3389
lime brkn	3424
lime	3500
lime brkn	3621
lime	3656
shale	3696
lime brkn	3716
3716 Rot.TD = 3716 SLM	
shale dk	3726
shale green	3728
lime	3745
Total Depth.	

Top Viola 3728
 Penetration 17

Loaded hole w/1400' wtr be-
 fore drilling-in
 At 3745 hole filled 1400'
 to 1550' (150') in 2 hrs.
 Hole filled 1550' to 1700'
 (150') in 2 hrs.