


CITIES SERVICE OIL CO.
Hinshaw "A" No. 4

SEC. 2 T. 23 R. 10 W.
SW¹/₄ SE
330' N 330' E S¹/₄ Corner.

Total Depth. 3761
Comm. 5-14-42 Comp. 6-4-42
Shot or Treated.
Contractor. Corbett-Barbour Drilling Co.
Issued. 8-8-42

County Reno.



CASING

85/8" 252' cemented.
6 1/2" 3748' cemented.

Elevation.

Production. Pot. 1747 B.

Figures Indicate Bottom of Formations no wtr. B.H.P. Gauge

sand	100
red bed	130
red bed and lime shells	252
red bed, shale and shells	745
anhydrite	775
shale	785
shale & shells	920
anhydrite & lime	950
salt and shells	1210
shale and shells	1350
anhydrite and lime	1390
broken lime and shale	1440
lime and shale	1490
lime	1607
lime and shale	1750
lime	1825
broken lime	2180
lime and shale	2368
broken lime and shale	2458
lime and shale	2590
broken lime and shale	2735
shale	2775
lime	2978
lime and shale	3063
lime	3095
shale and lime	3193
shale	3275
lime	3575
lime and shale	3581
lime shale and chert	3617
shale and chert	3667
shale and lime shells	3703
shale and shells	3738
lime	3741
3741 Rot.T.D. = 3748 SLM	
chert and lime	3752
lime	3757
dolomite	3761
Total Depth.	

Corr. Top Viola 3744'
Penetration 17'

Show free oil 3757-59
1000' oil in 1/2 hour 3759-61

500 gal June 12, 1942
1500 gal June 13, 1942