


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

LEADER OIL CO.
Tom No. 7.

SEC. 11 T. 23 R. 10 W
SW SE SE
990' fr EL 330' fr SL SE $\frac{1}{4}$

Total Depth. 3755 $\frac{1}{2}$ '
Comm. 5-11-42 Comp. 6-2-42
Shot or Treated. 6-4-42 500 Gals.
Contractor. Riso Drig. Co.
Issued. 7-25-42

County. Reno



Rotary 0-3750
Cable 3750-55 $\frac{1}{2}$

CASING:
10 $\frac{3}{4}$ " 285' Cem.
7" 3750' Cem.

Elevation.

Production. BHPB Pot. 28,755B.
No wtr

Figures Indicate Bottom of Formations.

sand	47
sand & shells	300
shale & shells	665
red bed	755
anhydrite	800
shale & shells	1175
lime	1530
lime & shale	1725
lime	1745
shale & lime	1885
shale	1955
shale & lime	2145
lime	2175
shale & shells	2235
shale & lime	2705
shale	2785
lime	2915
shale	2960
lime	3075
shale	3100
lime	3170
lime & shale	3190
shale	3265
lime	3285
lime & shale	3335
lime	3599
chert & shale	3618
shale	3745
lime Viola	3755 $\frac{1}{2}$
Total Depth.	

Tops: K.C. lime 3250

Viola lime 3745

Cemented 7" csg

Loaded hole w/1100' wtr drld
to T.D. 3755 $\frac{1}{2}$. Top Pay 3755

Hole filled 1400' w/oil under
1100' wtr load in 8 hrs & 40
minutes. Acidized w/500 Gals.

Well flowed 59 bbls oil 1st
hr wide open; 43 bbls on $\frac{3}{4}$ "
choke; 21 bbls on $\frac{1}{2}$ " choke;
16 bbls on $\frac{3}{8}$ " choke, btm
hole pressure bomb potential
28,755 bbls, no wtr