

LEADER OIL CO.
Tonn No. 9.

SEC.11 T.23 R.10 W
SW NE SW

CORRECTED LOG

Total Depth. 3764 $\frac{1}{2}$ '
Comm. 7-1-42 Comp. 8-1-42
Shot or Treated.
Contractor. Ruso Drlg.Co.
Issued. 10-3-42 Rotary O-3757
Cable 3757-64 $\frac{1}{2}$

County. Reno



CASING:

10 $\frac{3}{4}$ " 291' Cem.
7" 3757' Cem.

Elevation.

Production. Pot.12,174 B.BHPB

Figures Indicate Bottom of Formations.

sand	60
shale & red bed	565
anhydrite	595
shale & shells	965
salt & shale	1160
shale & shells	1340
shale & lime	1550
lime sdy	1685
lime	1840
shale & lime	2610
lime	2970
shale	3030
lime	3220
shale	3305
lime	3585
chert & shale	3617
lime	3623
chert	3638
shale	3750
lime Misener	3753
lime Viola	3764 $\frac{1}{2}$
Total Depth.	

7" csg 3757 Cem., drld TD
3764 $\frac{1}{2}$, Hole filled 3000'
over 400' wtr in one hr &
30 min. Acidized w/500 G.7-31-42
Flowed 55 bbl thru 1" choke,
27 bbl 3/4" choke, 24 bbls
1/2" choke, 13 $\frac{1}{2}$ bbl 3/8" choke
Btm Hole pressure bomb Pot.
12,174 bbls.

3763 $\frac{1}{2}$ -64 $\frac{1}{2}$ hole filled 3000' over
400' wtr 1 hr & 30 min.

Top Viola 3753
Pay 3763 $\frac{1}{2}$ -64 $\frac{1}{2}$