


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CITIES SERVICE OIL CO.
Heylman "C" No. 2.

SEC.12 T.23 R.10 W
SWc NE
330'N 330'E of Center

Total Depth. 3758'
Comm. 1-15-43 Comp. 2-15-43
Shot or Treated. 2-18-43 250 Gals.
Contractor. Corbett-Barbour Drlg.Co.
Issued. 4-10-43

County. Reno



CASING:
10 3/4" 192' Cem.
7" 3746' Cem.

Elevation.

Production. Phy.Pot.472 B.
no wtr

Figures Indicate Bottom of Formations.

sand	0-130
red bed	185
lime shells	192
shale & shells	1210
salt	1290
shale	1440
lime & shale	1490
lime	1580
lime sdy	1625
lime	1818
lime brkn	1863
lime	2120
shale & lime	2195
lime brkn	2327
shale	2397
shale & lime	2493
lime	2572
lime brkn	2614
lime & shale	2678
lime	3065
lime & shale	3176
lime brkn	3214
shale & lime	3252
lime	3514
lime w/strks chert	3552
lime	3592
chert	3605
lime & shale	3611
brkn lime w/chert	3642
shale	3739
lime	3743
3743 Rot.TD=3749 SIM	
lime & dolomite	3758
Total Depth.	

Corr. Top Viola 3744
Penetration 14

Loaded hole w/300' wtr
before drlg.shoe.
Good sh free oil 3756-58;
no fillup