


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

BARNSDALL OIL CO.
Maude Blasdel No. 3.

SEC. 13 T. 23 R. 10 W
S. SE ~~SW~~ NW

Total Depth, 3768' DF
Comm. 10-9-42 Comp. 11-18-42
Shot or Treated.
Contractor, Parker Drlg. Co.
Issued. 12-19-42

County. Reno



CASING:
10 1/2" 314.53' DF Cem.
7" 3760' DF Cem.

Elevation.

Production. Pmp 25 BO

Figures Indicate Bottom of Formations. (cutting 44%) in 8 hrs

surface sand	155
red bed & sand stone	325
red bed & shale	780
shale & shells	1315
shale & lime	1440
shale & shells	1541
shale & lm shells	1720
sand	1735
lime	1745
lime brkn	1910
shale & lime	1968
brkn lime & shale	2105
shale & lime	2345
shale & shells	2430
lime	2665
shale & shells	2750
shale	2755
lime	3076
lime brkn	3148
shale & lime	3212
shale	3218
lime	3237
lime brkn	3309
lime	3337
lime brkn	3449
lime	3564
shale	3585
chat & chert	3622
chert	3635
lime & shale	3654
shale	3696
shale & shells	3734
shale	3760
lim	3766
chert	3768 DF
Total Depth.	

10-21-42 Pmpd 35 BO (cutting
43%) in 9 hrs (Stats Pot. 34 B.)
10-22-42 Pmpd 25 BO (cutting
44%) in 8 hrs - 20 RPM at 44"