

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

SINCLAIR PRAIRIE OIL CO.
Geoil C. Crandall No. 1

SEC. 14 T. 23 R. 10 W
CNW SE
638'f N&W lines NW $\frac{1}{4}$ SE $\frac{1}{4}$

Total Depth. 3767
Comm. 7-12-42 Comp. 7-27-42
Shot or Treated.
Contractor. Harbar Drilling Co.
Issued. 9-5-42

County Reno.

Rotary.

CASING.

85/8" 290'

5 $\frac{1}{2}$ " 3762'

Elevation.

B.H.B.

Production. Pot. 5435 B.

Figures Indicate Bottom of Formations. for Max. Pot. 3000B.
no wtr.

sand	123
red bed and shale	860
shale and shells	1050
salt and shale	1220
shale	1395
shale and shells	1400
lime and shale	1505
shale	1620
lime and shale	1692
sand and lime	1765
shale and lime	2265
lime broken	2490
shale and lime	2580
lime broken	2705
lime and shale	2805
lime	3010
shale and lime	3210
shale	3280
shale and lime	
chert	3330
shale and lime	3410
shale and lime	
chert	3450
shale and lime	3565
lime and chert	3600
chert	3630
lime	3640
shale	3760
lime	3767

Total Depth.

All Meas. corrected to Rig floor.

Top Viola 3760

Good oil show 3762-65

Oil fillup 200' first 30 min, 1100' next 30 min, Total 1300' first hr.
Total 3000' in 2 hours.

Temporary test 8-3-42 Potential 125 bbls.,

Acidized 8-7-42 with 300 gal.

Test following with bottom hole bomb, made 5435 bbls oil
for a Max. pot. of 3000 oil no water 8-10-42