

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

SINCLAIR PRAIRIE OIL CO.
Cecil C. Crandall No. 3.

SEC.14 T.23 R.10 W
CSW SE
554'f N & E Lines SW $\frac{1}{2}$ SE $\frac{1}{4}$

Total Depth. 3770'

Comm. 11-22-42

Comp. 12-18-42

Shot or Treated.

Contractor. Harbar Drlg.Co.

Issued. 3-6-43

Rotary 3758

Cable 3770

County. Reno



CASING:

8 5/8"

296' Cem.

5 1/2"

3756' Cem.

2 1/2"

3787' Cem.

Elevation.

Production. Pot. 2301 B.
No wtr

Figures Indicate Bottom of Formations.

sand & shale	130	After 500 Gals. Acid pmpd
red bed & shale	300	temp. Pot. 461 BO (153.60
red bed & shells	500	bbl in 8 hrs)
shale-shells	785	12-30-42 took draw down
shale & shells	1200	test pmpg w/btm hole
shale-lime shells	1440	bomb, made 2,301 bbls
shale-brkn sdy lime		oil, no wtr
shells	1560	
lime & shale	1640	
lime	1800	
lime & shale	1860	
lime	1925	
shale & lime shells	1965	
shale & lime	2120	
lime shells & shale	2215	
brkn lime & shale	2270	
shale & lime	2360	
shale-lime shells	2440	
shale & lime	2450	
shale	2455	
shale & lime shells	2645	
shale	2756	
lime	2784	
shale	2800	
lime	2965	
shale	2990	
brkn lime & shale	3054	
shale	3210	
lime	3220	
lime & shale	3305	
lime	3355	
lime brkn sdy	3395	
lime	3490	
lime & shale	3535	
lime	3610	
chert	3638	
shale	3756	
lime	3763	
shale	3764	
oil show 3766-70		
lime	3770	
Total Depth.		

Tops:

Lansing-K.C. 3258

Miss. Chert 3385

Viola 3754