


CITIES SERVICE OIL CO.
Endicott No. 1.

SEC.14 T.23 R.10 W
CNE SW
660' S 660' W of Center

Total Depth. 3775'
Comm. 8-28-42 Comp. 9-16-42
Shot or Treated. 300 Gals. 9-29-42
Contractor. Helmerich & Payne, Inc.
Issued. 12-12-42

County. Reno



CASING:
8 5/8" 156' Cem.
5 1/2" 3769' Cem.

Elevation.

Production. BHP Gauge Pot.
2940 BO, 60 BW
(Ind. Cap. 7349 B.)

Figures Indicate Bottom of Formations.

surface loam & sand	0-125
shale & shells	156
red bed & shale	980
shale, sand, salt	1200
shale & shells	1290
anhydrite & shale	1460
lime & shells	1570
sdv lime & shale	1670
sand, lime & shale	1777
shale & shells	1946
lime & shale	2113
shale & shells	2245
shale & lime	2380
lime & shale	2507
lime & shells	2580
shale & lime	2710
lime & shale	2761
lime Topeka	2810
lime	2865
lime & shale	2907
lime	3050
lime & shale	3085
lime brkn	3130
brkn lime & shale	3229
shale & lime	3285
lime	3548
lime & shale	3591
chert & lime	3628
lime	3680
shale & lime	3763
lime	3769
3769 Rot. TD = 3773 SIM	
lime	3775
Total Depth.	

Corr. Top Viola 3766
Penetration 9'

Loaded hole w/2000' wtr
before drlg shoe
At 3775 hole filled 2000'
to 2300' (300') in 1 hr
9-29-42 Temp. Phy. Pot. -
346 oil, no wtr, 24 hrs.,
natural