


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

REPUBLIC NATURAL GAS CO.
Werner No. 2.

SEC.15 T.23 R.10 W
SW NE NW

Total Depth. 3771'
Comm. 4-27-42 Comp. 5-21-42
Shot or Treated. 5-20-42 3000 Gals.
Contractor. E.K. Carey
Issued. 7-26-42 Rotary O-3755
Cable 3755-71

County. Reno



CASING:
8 5/8" 215'10" Cem.
5 1/2" 3754' Cem.

Elevation.

Production. Pot. 1260 BO,
No wtr

Figures Indicate Bottom of Formations.

surface clay & sand	31
sand	90
red rock	437
anhydrite	458
shale	1080
salt & shale	1300
shale & shells	1440
lime	1750
lime sdy	1784
lime	1828
lime & sdy lime	1888
lime & shale	2338
lime brkn & shale	2437
shale & lime	2518
lime brkn	2575
lime & shale	2788
lime	2860
lime brkn	2903
lime	3091
lime brkn	3157
lime & shale	3251
lime brkn	3270
lime	3426
lime sft & porous	3434
lime	3463
lime brkn	3510
lime	3606
lime cherty	3629
shale & lime	3659
lime	3693
conglomerate	3749
Viola	3764 $\frac{1}{2}$
Viola sft	3771
Total Depth.	

Top Viola 3749