

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

36-23-11W

Company - DERBY OIL & D.R.M.
Farm - Smart No. 2

SEC. 36 T. 23 R. 11 W
NE NW NE

Total Depth. 3732'

Comm. 5-7-44

Comp. 5-23-44

Shot or Treated.

Contractor. Sharon Drlg. Co., Inc.


Issued. 8-5-44

Rotary 0-3697

Cable 3697-3732

County.

Stafford
KANSAS



CASING:

8 5/8"

244' Cem.

5 1/2"

3694' Cem.

Elevation. _____

Production.

Dry

Figures indicate Bottom of Formations.

sand	160
red bed	480
anhydrite	505
shale & shells	980
shale & salt	1185
shale & shells	1285
lime brkn	1795
sand	1820
lime brkn	1900
lime	1960
shale & lime	2030
lime	2065
shale & shells	2075
shale	2190
lime brkn	2238
shale shells	2340
shale	2560
lime brkn	2710
lime	2765
shale	2818
lime	3140
lime & shale	3180
sand	3205
shale	3311
lime	3525
lime & shale	3605
shale	3630
lime & shale	3670
shale	3674
lime	3688
lime & chert	3700
lime	3732
Total Depth.	

Tops:

Lansing 3306

Misener 3652

Viola 3671

3700=3697

DP DD 3710, stn oil 3708 500
A. @ 3710' bail 1/4 BO & 1LWPH 2
hrs. DD 3732 2000 A. 600# press.
Swb 2 3/8 fluid PH 2hrs. 75% wtr.
SD 12 hrs. 240' fluid. Swb 1 1/2 BO

* 2 1/2" H & swb Dwn. Swb 5 1/2 BO & 15
HW 15 hrs.

Perf. 66/3569-94 500 A. Perf. 61/
3648-67, swb 12 hrs. 1LWPH Perf.
11/3521-32, 12/3527-31 no shows