

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


36-23-11W

Company - REPUBLIC NATURAL GAS CO.
Farm - M. Volker No. 2.

SEC. 36 T. 23 R. 11 W
CE 1/2 SW SW

Total Depth. 3735.
Comm. 9-15-44 Comp. 10-16-44
Shot or Treated.
Contractor. Gabbert Drlg. Co.
Issued. 4-28-45 Rotary O-3720
Cable 3720-3735

County. Stafford
KANSAS



CASING:
10 3/4" 326'2" 324' LI Cem.
5 1/2" 3716'

Elevation. _____

Production. Pot. 39 B.

Figures Indicate Bottom of Formations.

sand	0-175
red bed	295
sand	315
sand, shale & shells	324
red bed, shale	505
anhydrite	530
shale	700
shale & salt	1040
shale & shells	1380
anhydrite	1410
shale & shells	1415
lime	1540
shale & shells	1650
shale	1740
shale & shells	1850
lime	1880
shale	1930
shale & shells	1950
lime	1980
shale	2000
shale & shells	2135
shale	2145
shale & shells	2420
shale	2435
lime & shale	2455
shale	2495
shale & shells	2655
lime	2775
shale shells	2840
lime	2890
lime - Topeka	2990
lime	3225
K. C. Lime	3295
lime	3715
lime	3720
3' SIC	3717
lime	3735
Total Depth	

Top:
Mazon 3696
Viola 3711 DF

10-14-44 1500 Gals. Acid
10-16-44 2000 Gals. Acid