

SOUTHEAST GARFIELD PROSPECT

State Kansas County Pawnee

Company Messman-Rinehart Oil Co. Well No. 1


Farm Paramore (washdown)

Survey _____

Block No. _____ Sec. 11 Twp. 23 S Range 17 W

Co-Ord. _____ Elev. _____

M-R Rig



34% - A. A. Seeligson, Jr.
 16% - Ramona Frates Seeligson
 25% - L. J. Plym
 25% - Messman-Rinehart Oil
 ORI - Karl E. Becker
 Washdown of Woodman-Iannetti
 #1 Paramore - 8-5/8" @ 256'
 4220' Cong. test to be comm
 by

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
11/20/65		M.I.R.T.
11/22	4285	C.O. Depth
11/23		Ran log (had difficulty getting hole conditioned)
		DST #1 - 4237-58' - Op 1 hr., good bl. decr. & died in 32", Rec. 3045' wtr. (sulfur), SIP (30") 1379-1379# FP 959=1379#, Temp. 108°
		DST #2 - 4198-4236' - Op 1 hr 15", fr. bit

Date	Depth	694444
		Rec. 300' wtry mud w/spots of tar
		SIP (30") 1450-(45") 1347#, FP 47-14
		Temp. 107°
		DST #3 - 4058-4100 - Op 1 hr., GTS in 3",
		Ga. 686 Mcf/5"; 734 Mcf/10",
		Means BTU 802 Mcf/20", 857 Mcf/30", 917 Mcf/
		1058 Gross 40", 943, Mcf/50", 971 Mcf/60"
		958 Net BHP (30") 1324-(45") 1292#,
		FP 126-189#, Rec. 180' GCM & 20'
		thin GCM, Temp. 108°
		4284 R.T.D. (ran log)
		4½" @ 4150' w/150 sx., P.D.
		@ 7:15 a.m. 11/25/65
11/27		M.I.C.T.
11/29		Perf. 4078 - 1 ^s (bullet)
		Perf. 4081 - 1 ^s (bullet)
		Tested 1,120 Mcf
11/30		Perf. 4072-83' w/4 ^s ft.,
		300 mud acid
12/1		Tested 500,000 cfg
12/2		Frac 15,000# sd., 560 BW
		Broke & fed in @ 2100# at rat
CSG (Wichita)		of 11 bbls/min., KO & fl on
BTU 997		about 6th swb (esti. 5,000 Mc
12/6		64-hr SIP - 1091#
		Merle spring-gauge op fl
		2,500 Mcf/gd,
		12/2/65 - SI for conn.