


COMPANY SKELLY OIL COMPANY

SEC. 29 T. ²³~~31~~ R. 12W
LOC. SW NW SE
990' FNL, 330' FWL, W/2, SE/4

FARM V.L. Williamson NO. 2

TOTAL DEPTH 3912
COMM. 11-9-50 COMP. 11-24-50
SHOT OR TREATED
CONTRACTOR Claude Wentworth Drlg Co., Inc.
ISSUED 12-23-50

COUNTY Stafford
KANSAS



CASING
8 5/8" 685' cem w/ 300 sx.

ELEVATION 1871 DF

PRODUCTION dry

FIGURES INDICATE BOTTOM OF FORMATIONS

surface soil, sand, clay	70
sand	135
clay, shells	280
red bed, shells	670
anhydrite	685
shale, lime	2995
lime	3240
lime, shale	3480
lime	3615
lime, chert	3735
lime, shale	3865
shale	3882
dolo., fine xyn	3888
slight porosity & spotted oil stain	3882-3888
dolo. coarsely xyn	
grey	3912
Good porosity, no shows	
Total Depth	

Tops:

Anhydrite	685
Heebner Shale	3259
Toronto Lime	3279
Douglas Sand	3304
Brown Lime	3398
Lansing Lime	3427
Conglomerate	3710
Viola Lime	3747
Simpson Shale	3811
Arbuckle Lime	3882

Ran Halliburton drill stem test, packer set @ 3882', open 1 hr., recovered 735' of water, no oil or gas.

No commercial quantities of oil or gas.