


28-23-12W

THE TEXAS CO.
M. Gerdes No. 2.

SEC.28 T.23 R.12W
SE NE SW

Total Depth. 3858'
Comm. 7-13-41 Comp. 8-14-41
Shot or Treated. 1500 Gals. Acid
Contractor. Warren & Bradshaw
Issued. 9-20-41 Rotary O-3854
Cable 3854-58

County. Stafford



CASING:

10 $\frac{3}{4}$ " 240' Cem.
5 $\frac{1}{2}$ " 3854' Cem.

Elevation. 1866

Production. Pot. 1768 B. Echo
13% Wtr

Figures Indicate Bottom of Formations.

sand & red bed	240
red bed, sand, shale	500
red bed & shale	1325
shale & shells	1540
brkn lime & shale	1575
shale & lime	1655
lime	1780
lime & shale	1870
lime brkn	2000
lime	2030
shale & shells	2065
shale & lime	2250
lime	2275
shale	2325
shale & shells	2390
shale & lime	2585
shale sticky	2670
shale & lime	2930
lime	2952
shale & lime	2990
lime	3070
shale	3099
lime	3130
shale & lime	3185
lime hrd	3198
shale sticky	3202
shale & lime	3424
lime brkn	3515
chert hrd & lime	3520
lime brkn	3570
shale sdy	3590
lime brkn	3600
shale & lime	3633
lime hrd & shale	3687
lime	3723
lime & shale	3746
chert	3751
chert & lime	3785
shale & lime	3830
cored	3858
Total Depth.	