

THE TEXAS CO.
M.Gerdes No. 3.

28-23-12W
SEC.28 T.23 R.12W
NW SE SW

Total Depth. 3860'


Comm. 8-30-41 Comp. 9-23-41

Shot or Treated.

Contractor. Warren & Bradshaw Drlg.

Issued. 10-25-41 Rotary O-3858
Cable 3858-60

County. Stafford



CASING:

10 $\frac{3}{4}$ " 286' Cem.
5 $\frac{1}{2}$ " 3858' Cem.

Elevation.

Production. Pot. 15 B. Min.

Figures Indicate Bottom of Formations.

sand	120
shale red, gyp, shells	235
shale & red bed	355
red bed	375
red bed, sand, shale	975
shale & shells	1515
lime brkn	2030
lime hrd	2105
lime brkn & shale	2350
shale & limo	2700
lime brkn	2785
shale & shells	2820
shale & limo	2885
sand	2911
shale	2925
lime	2940
shale	2983
limo & shale	3192
lime hrd	3212
lime	3297
lime & shale	3428
lime	3495
lime & chert	3531
lime	3538
shale & limo	3581
sdv shale	3590
lime hrd	3602
lime	3708
lime w/chert	3732
lime & chert	3776
chert	3795
shale & limo	3822
dolomite	3827
shale	3858
limo brkn	3860
Total Depth.	

Perforated pipe from 3846 to 58 -
36 holes & from 3822 to 34 - 36
holes

Jetted 1000 Gals. Acid - and 500
Gals. Acid before and after jet
Took swb test and established 15
bbl. min. well.

Top Arbuckle 3858