


28-23-12W

HARRY GORE(SHELL OIL CO.,INC.)
Floyd Heyen "B" No. 1.

SEC.28 T.23 R. 12 W
NW SE NW
990'f SL 990'f EL NW $\frac{1}{4}$

Total Depth. 3852'
Comm. 12-4-41 Comp. 1-20-42
Shot or Treated.
Contractor. Mercury Drlg.Co.
Issued. 2-7-42

County. Stafford



CASING:
8 5/8" 311' Cem.
5 1/2" 3841' Cem.

Elevation.

Production. Pot.203 B.
166 BW,Pmp

Figures Indicate Bottom of Formations.

sand	100
sand & clay	200
red rock	300
lime shells	322
red rock	683
anhydrite	705
shale & shells	981
shale & lime shells	1160
salt & shale	1440
shale & lime	1705
shale & lime shells	1797
lime brkn	1911
lime	2051
shale & lime shells	2161
lime	2270
shale & lime	2435
sand & lime	2450
lime brkn	2564
shale & lime	2995
lime	3279
shale	3340
shale & lime	3456
lime brkn	3518
shale & lime	3610
lime brkn	3703
limo & shale	3725
chert	3748
chert & lime	3772
shale	3840
limo	3842
dolomite	3852
Total Depth.	

Top Arbuckle dolomite 3842

Acidized 500 Gals.1-15-42

No show oil or water after drilling cement plug
and cleaning out 3242.

1300' of oil and 3 BW at bottom after 20 hrs.

1-1-42 2400' of fluid 47 $\frac{1}{2}$ hours bail 2 $\frac{1}{2}$ BW