


CITIES SERVICE OIL CO.
Knoche No. 2.

28-23-12W
SEC.28 T.23 R. 12 W
NW NE SE
330'S 990'W E $\frac{1}{4}$ Cor.

Total Depth. 3840'
Comm. 10-18-41 Comp. 11-7-41
Shot or Treated. None
Contractor. Corbett-Barbour Drlg.Co.
Issued. 12-13-41

County. Stafford



CASING:
8 5/8" 310' Cem.
5 1/2" 3830' Cem.

Elevation.

Production. Deptho.Pot.3000B.

Figures Indicate Bottom of Formations. No wtr(Ind.Cap.3564 B.)

sand & shells	0-125
lime shells & shale	310
rod bed	920
redrock & shale	1175
salt & shells	1325
salt & shale	1370
shale & shells	1460
anhydrite	1495
lime brkn	1590
shale & shells	1737
anhydrite & lime	1878
lime brkn	1935
lime & chert	1955
lime brkn	2370
shale	2523
lime brkn & shale	2651
shale	2705
lime	2745
lime brkn	2905
lime	3188
shale	3200
lime	3335
lime & shale	3390
lime brkn	3437
lime(S.O. 3570-80)	3719
chert & lime	3726
lime	3737
chert	3761
lime	3766
shale	3790
shale & lime	3833
dolomite	3835
3835 Rot.TD = 3831 SLM	
dolomite	3840
Total Depth.	

Corr. Top Arbuckle 3829
Penetration 11

Fillup:
500' oil in 2 hrs at 3835
1250' oil in 6 hrs at 3835
1700' oil in 12 hrs at 3835
2100' oil in 15 hrs at 3838
3800' oil in 17 hrs at 3840