


THE BRITISH-AMERICAN OIL PRODUCING CO.
Roy Meyer No. 2

28-23-12W
SEC. 28 T. 23 R. 12W.
NW SW NE
1650' S of NL 330' E of WL
NE $\frac{1}{4}$

Total Depth. 3841
Comm. 12-29-40 Comp. 1-20-41
Shot or Treated.
Contractor.
Issued. 2-22-41.

County Stafford.



CASING.

9" 300' cemented.
5 $\frac{1}{2}$ " 3828' cemented.

Elevation.

Production. Pot. 3235 B.

Figures Indicate Bottom of Formations.

sand	130
sand and shells	185
red beds	304
shale shells and red bed	658
anhydrite and lime	679
anhydrite	696
red bed and shells	835
shale shells and red beds	990
shale and lime	1140
red bed & shells	1150
salt	1190
red bed shale and shells	1498
lime	1635
broken lime	1724
pyrite and lime	1758
lime and shale	1820
broken lime	1865
sdv lime	1905
lime and shale	1910
lime	2025
lime and shale	2936
lime	3185
broken lime	3205
lime and shale	3368
lime	3375
broken lime	3394
lime	3425
lime and shale	3468
lime	3665
lime and chert	3693
shale and chert	3722
chert	3758
chert and shale	3776
shale and sand	3818
shale green and sdv green shale	3828
Arbuckle lime	3839
sdv lime and green shale	3841
Total Depth.	

Top of Arbuckle 3828