

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
 412 Union National Bk Bldg, Wichita, Kansas.


28-23-12W

THE BRITISH-AMERICAN OIL PROD.CO.
 R.Meyer No. 6

SEC. 28 T. 23 R. 12 W.
 SEc NE
 330' W EL 330' N SL NE $\frac{1}{4}$

Total Depth. 3843 (3838 Gr.L.)
 Comm. 12-21-41 Comp. 1-13-42
 Shot or Treated.
 Contractor.
 Issued. 5-16-42

County Stafford.



CASING.

9" 341' cemented.
 5 $\frac{1}{2}$ " 3815' cemented.

Elevation.

Production. Pot.4083 B.
 Drawdown.

Figures Indicate Bottom of Formations.

sand and red bed	160
shale and lime shells	277
sand	295
shale and lime shells	347
red bed, shale and shells	1370
salt	1565
shale and shells	1640
anhydrite	1740
shale and lime	2250
shale and shells	2680
shale and lime	3390
lime and shale	3719
show of oil in Kansas City from 3473-3481, and from 3556-3566	
chert, lime, sand and shale	3818
slight show of oil in Viola lime from 3728 to 3732	
shale and dolomite	3840
show of oil in dolomite	3820-24
Arbuckle lime	3843 show oil 3840-43
	3838 Total Depth corrected to Ground level.

Top Kansas City 3390
 Arbuckle 3835

Note: All above measurements are ground level.