

16-23-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- D. R. LAUCK OIL CO., INC.
Farm- Schulz "B" No.1

SEC. 16 T. 23 R. 13W
SE SE SW

Total Depth. 3945
Comm. 7-2-55 Comp. 7-15-55
Shot or Treated.
Contractor.
Issued. 8-27-55

County Stafford
KANSAS



Elevation. 1878 DF

Production. Dry

CASING:

- 8 5/8 162' w/ 165 sx cmt.

Figures indicate Bottom of Formations.

sand	70
- shale & shells	205
sand	280
red bed & sand	755
anhydrite	780
red bed, shale & shells	940
red bed & shale	1025
salt & shale	1115
lime & shale	1375
shale & shells	1600
shale & lime	2130
broken lime	2275
lime & shale	2380
shale	2415
lime & shale	2540
shale & shells	2810
lime & shale	3267
lime	3277
lime & shale	3458
lime	3708
lime & shale	3775
lime	3945
Total Depth	

TOPS:	SAMPLE	HALLIBURTON
Anhydrite	755	
Heebner	3314	3313
Brown lime	3449	3448
Lansing	3470	3470
Base KC	3720	3724
Marmaton chert	3737	3730
Viola	3807	3810
Simpson	3843	3851
Arbuckle	3904	3903

DST #1: 3493-3520, open 20 min. wk.
bl. 7 min. rec 15' mud, BHP 1140#/20 min.

DST #2: 3652-70, open 1 hr. wk. bl:
40 min. rec. 30' mud w/ oil specks,
BHP 98#/20 min.