

32-23-13W


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CROWN OIL CO., & LOTUS OIL CO.
Farm - Williams No. 3

SEC. 32 T. 23 R. 13W
NE NE SW

Total Depth. 3673
Comm. 4-11-49 Comp. 4-28-49
Shot or Treated.
Contractor. Crown Oil Co., Inc.
Issued. 6-11-49

County. Stafford
KANSAS



Elevation. 1909 *Ind*

Production. Draw Down Pot. 1324

CASING:
8 5/8" 317' cem w/150 sx.
5 1/2" 3665' cem.

Figures Indicate Bottom of Formations.

cellar	4
surface clay, and	
sand	40
surface sand, shale	313
red bed, shale and	
shells	700
red bed, shale	788
anhydrite	810
red bed, shale	960
shale	1100
shale, shells	1275
shale	1325
salt, shale	1445
shale, shells	1700
lime, shale	1870
lime brkn	1965
lime, shale	2565
shale, shells	2670
lime, shale	2885
lime brkn	3030
lime	3135
lime, shale	3555
lime	3673
Total Depth	

Tops:

Heobner shale 3380
Lansing (white) 3542

REMARKS:

Soft zones carrying poor to fair porosity, but lacking odor and oil shows wer logged 3652-3571; 3576-3580 and 3606 to 3614.

Pay Zone: The Lansing pay zone in the #3 Williams from 3666 to 3673 is comparable in datum (-1757) to the #1 (-1752) and #2 Williams (-1756).

The pay samples in #3 Williams carried good staining and excellent porosity. It was recommended that casing be run on the above premises without a DST.