

36-23-14W ✓

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- RANGE OIL
Farm- VanHoozer

No. 1

SEC. 36 T. 23 R. 14W
SW NE SW

Total Depth. 3865'

Comm. 10-9-64


Comp. 10-17-64

Shot or Treated.

Contractor. Graves Drlg.

Issued. 2-13-65

County Stafford
KANSAS



CASING:

8 5/8" 238' cem w/ 250 sx

4 1/2" 3863' cem w/ 125 sx

Elevation. 1942' KB

Production. 28 BOPD 35% WTR

Figures indicate Bottom of Formations.

sand & shale	238
shale & shells	849
lime & shale	870
shale	958
shale & shells	1690
lime & shale	2120
lime	2250
lime w/ shale	2300
shale w/ lime	2707
lime & shale	3506
shale & lime	3578
Brown lime	3582
shale & lime	3856 RTD
Total Depth	

TOPS: SCOUT

Heebner	3438
Brown lime	3580
Lansing	3602
Base Kansas City	3852