

JAMES C. MUSGROVE

Petroleum Geologist

2021 Forest

P.O. Box 1162

Great Bend, KS 67530

ORIGINAL

Office (316) 792-7716

Res. Claflin (316) 587-3444

K C C

Computer Inventoried

MAR 19 1998

L.D. Drilling, Inc.
Seibert #1
NE-SW-SE
Section 6-23s-14w
Stafford County, Kansas
Page No. 1

15-185-23044

Dry and Abandoned

Contractor: Company Tool (Rig #1)

Commenced: February 28, 1997

Completed: March 6, 1997

Elevation: 1979' K.B., 1976' D.F., 1974' G.L.

Casing Program: Surface; 8 5/8" @ 362'
Production; None

Samples: Samples saved and examined 2800' to the Rotary Total Depth.

Drilling Time: One (1) ft. drilling time recorded and kept 2800' to the Rotary Total Depth.

Measurements: All depths measured from the Kelly Bushing.

Formation Testing: None.

Electric Log: None.

<u>Formation</u>	<u>Sample Depth</u>	<u>Sub-Sea Datum</u>
Anhydrite	918	+1061
Howard	2971	-992
Topeka	3043	-1064
Heebner	3446	-1467
Brown Lime	3578	-1599
Lansing	3589	-1610
Base Kansas City	3831	-1852
Conglomerate	3906	-1927
Conglomerate Chert	3957	-1978
Viola	3981	-2002
Simpson Shale	4066	-2087
Arbuckle	4124	-2145
Rotary Total Depth	4136	-2157

(All tops and zone determinations were made from a correlation of drilling time log and sample analysis.)

SAMPLE ANALYSIS, SHOWS OF OIL, TESTING DATA, ETC.**HOWARD SECTION**

2971-2990' Limestone; gray to white, medium crystalline, slightly dolomitic, few fossiliferous, fair pin point to intercrystalline to vuggy type porosity, no stain, no show of free oil, questionable gas bubbles, spotty poor fluorescent.

3008-3016' Limestone; gray, fossiliferous, slightly chalky, no shows.

TOPEKA SECTION

3043-3446' There were several zones of well developed porosity encountered in the Topeka Section but no show of oil or gas were noted. (See sample log.)

RECEIVED
KANSAS CORP. 00101
1997 MAY 29 A 12:48

TORONTO SECTION

3470-3484' Limestone; white to gray, fossiliferous, chalky in part increasingly finely crystalline dolomitic limestone at base, poorly developed porosity, no shows.

LANSING SECTION

3590-3594' Limestone; white to tan, fossiliferous in part, poorly developed porosity, no shows.

3611-3619' Limestone; gray, slightly oolitic, chalky increasingly cherty with depth, scattered porosity, trace tan to gray chert.

3630-3636' Limestone; gray to white, fossiliferous, chalky, poor porosity, no shows.

3657-3664' Limestone; gray, fine to medium crystalline, fossiliferous in part, fair vuggy to intercrystalline porosity, dull gray spotty stain, no show of free oil or odor in fresh samples.

3571-3680' Limestone; oolitic, oocastic, fair to oocastic porosity, no shows.

3682-3698' Limestone; as above, no shows.

3713-3722' Limestone; gray to tan, oocastic, fair oocastic porosity, no shows. (Remarks; 'H' zone is 13' low to Boger/Seibert #1)

3739-3746' Limestone; gray to tan, fossiliferous, slightly granular, poorly developed porosity, chalky in part, no shows.

3764-3772' Limestone; white, fine to medium crystalline, oocastic, good vuggy to oocastic porosity, no shows.

3785-3790' Limestone; white to gray, oolitic, finely oocastic, fair oocastic porosity, no shows.

3794-3804' Limestone; gray to white, fossiliferous, chalky, black clear stain, no show of free oil or odor in fresh samples.

3822-3826' Chert; tan to dark brown, boney to opaque, no shows.

CONGLOMERATE SECTION

3957-3974' Chert; white to gray, boney, slightly weathered, black dead stain, no show of free oil or odor, plus tan to orange chert, no shows.

VIOLA SECTION

3981-4000' Cherty; white to gray, boney, few tripolitic scattered porosity, black stain, trace of free oil and no odor in fresh samples.

4000-4020' Chert; as above, chalky luster, black stain, trace of free oil and no odor.

4020-4040' Chert; as above, plus gray to white, cherty dense limestone, no shows.

4040-4066' Limestone; and chert as above, few pieces limestone green tinted, no shows. (Remarks; the Viola Section is 28 ft. low to the Boger/Seibert well 660' west of location, the Viola Section was tested in the Boger well with negative results.)

SIMPSON SECTION

4084-4090' Sand; green, very fine grained, shaley, dolomitic, no shows.

4116-4124' Sand; very fine to medium grained, shaley, poorly developed, no shows.

ARBUCKLE SECTION

4124-4136' Dolomite; tan to gray to pink, fine to medium crystalline, poor visible porosity, cherty in part, pyrite inclusions, no shows.

RECEIVED
KANSAS CORP. CORP.
1997 MAY 29 12:48

L.D. Drilling, Inc.
Seibert #1
NE-SW-SE
Section 6-23s-14w
Stafford County, Kansas
Page No. 3

Rotary Total Depth 4136 (-2157)


Remarks:

During the drilling of the Seibert #1 it was compared structurally to the Boger Brothers, Seibert #1, located NW-SW-SE, Section 6-23-14w. This well is 660' west of the LD Drilling Seibert #1. L.D. Drilling Seibert #1 was 2' low on Anhydrite, Heebner - 11', Brown Lime - 14', Base Kansas City - 18', Viola - 28', Simpson Shale - 35', and Arbuckle was -42'.

Recommendations:

On the basis of the low structural position and there being no other zones worthy of any further testing, it was recommended by all parties involved to plug and abandon the Seibert #1 at the Rotary Total Depth 4136 (-2157).

Respectfully submitted;


James C. Musgrove
Petroleum Geologist

RECEIVED
KANSAS OIL & GAS
MAY 29 4 12 48