

11-23-14W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- NATURAL GAS & OIL CORPORATION AND
Farm- REPUBLIC NATURAL GAS CO.
Oscar Miller No. 1

SEC. 11 T. 23 R. 14W
SE SE NW

Total Depth. 3984'

Comm. 2-17-54


Comp. 3-1-54

Shot or Treated.

Contractor. Drilling Department of Natural Gas & Oil Corp.

Issued. 4-10-54

County Stafford
 KANSAS



CASING:

8 5/8" 195' cem w/225 sx

Elevation. 1946' RB

Production. Dry

Figures indicate Bottom of Formations.

sand & clay	160
shale & shells	300
sand	360
shale & shells	550
red bed & shale	842
anhydrite	880
shale & shells	1075
shale with salt	1300
shale & shells	1675
shale & lime	1725
lime	2420
lime & shale	3035
lime	3360
lime & shale	3507
brown lime	3511
lime & shale	3525
lime	3805
conglomerate	3860
lime & chert	3918
lime	3925
shale	3966
lime	3984
Total Depth.	

Tops:

Anhydrite	842
Hebner	3378
Brown Lime	3507
Lansing	3525
Base Kansas City	3754
Viola	3857
Simpson	3923
Arbuckle	3967

DRILL STEM TESTS:

#1 3642-58, open 1 hr, SI 30 min., wk blow
4 min, rec. 20' mud, 0# IFP, 0# FFP,
1260# BHP.

#2 3674-3706, open 1 hr, wk blow thruout,
rec 100' watery mud, SI 30 min, 0# IFP
0# FFP. 880# BHP

#3 3865-3918, open 1 hr, SI 30 min, IFP 0#
FFP 0#, BHP 0#.

#4 3971-84, open 1 hr, good blow, 2880'
sulphur water, SI 30 min, 150# IFP,
1150# FFP, 1200# BHP.

Ran Schlumberger
Dry, Plugged and Abandoned