

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

15-23-14W


Company - HUBER AND HARBAR
Farm - Coen

No. 1

SEC. 15 T. 23 R. 14W
SE SE SE

Total Depth. 4045'
Comm. 9-20-48 Comp. 10-9-48
Shot or Treated.
Contractor. Harbar Drlg.
Issued. 11-6-48

County. Stafford
KANSAS



CASING:

8 5/8" 425' cem w/225 Sx.

Elevation. 1934' Ind.

Production. Dry and abandoned

Figures Indicate Bottom of Formations.

shale and shells	290	3603-06 Slight show oil
sand	315	3610-22 " " "
sand and shale	354	D.S.T. 3604-31, Open 1 hr
shale	467	recovered 390' sat wtr.
sand	478	3673-79, Fair show oil.
shale and shells	515	D.S.T. 3674-81, open 1 1/2
shale	680	hr, recovered 30' mud.
shale and shells	1097	No shows.
lime shale	1371	3707-22, very slight SO.
shale and shells	1725	3739-47, " " "
shale and lime	1890	
lime	2060	
lime and shale	2282	
shale	2339	
shale, brkn	2465	
lime and shale hd	2617	
lime and shale brks	2692	
lime and shale	2895	
lime	2951	
lime and shale	3080	
lime hd	3139	
shale and lime	3273	
lime	3339	
lime and shale	3370	
sand, shale, lime brk	3424	
lime and shale brks	3500	
shale	3533	
lime	3560	
sand and lime	3602	
lime hd	3628	
lime	3635	
lime brkn brn lime	3663	
lime	3807	
shale & lime shells	3854	
shale and lime hd	3877	
lime soft	3885	
shale and lime hd	3896	
lime hd	3916	
lime and shale	3942	
lime and chert	3975	
lime hd	3995	
shale, lime hd	4045	
Total Depth		

Tops:

McDonner	3395'
Toronto	3416
Base Oread	3432
Brown Lansing	3532
Lansing	3549
Base S.C.	3792
Conglomerate	3863
Viola	3877
Simpson	3975
Abundant	4013

By: J. H. Amborger