

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

17-23-14W

COMPANY J. M. STEWART

SEC. 17 T. 23 R. 14W
LOC. 150' S of SE NE SE

FARM Cornwell

NO. 1

TOTAL DEPTH 3929

COMM. 3-8-67

COMP. 3-18-67


SHOT OR TREATED

CONTRACTOR Hellar Drlg.

ISSUED 4-8-67

COUNTY Stafford

KANSAS



CASING

20

10

15

8 5/8" @ 250' w/200 sx

ELEVATION 1983' KB

12

6

13

5

PRODUCTION DRY/KIND SAND

FIGURES INDICATE BOTTOM OF FORMATIONS

0-250	Surface Sand & Shale
250-875	Shale & Red Bed w/sand streaks
875-892	Shale
892-910	Anhydrite
910-1600	Shale, Red Bed & Salt Section
1600-1845	Shale & Lime
1845-2000	Salt Section & Cherty Lime
2000-2205	Cherty Lime
2205-2345	Cherty Lime & Shale
2345-3113	Lime & Shale
3113-3244	Topeka Lime & Shale
3244-3489	Lime & Shale
3489-3552	Shale
3552-3555	Shale & Lime
3555-3596	Lime
3596-3644	Lime & Shale
3644-3720	K. C. Lime
3720-3780	Lime
3780-3827	K. C. Lime
3827-3895	Lime
3895-3905	Miss. Chert & Lime
3905-3929	Sand
3929	Rotary Total Depth

TOPS: SCOUT

Anhydrite	892
Heebner	3421
Toronto	3439
Douglas	3456
Brown Lime	3552
Lansing	3565
Base Kansas City	3800
Mississippi	3874
Kinderhook Sand	3908

D & A

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Cornwell, located 150' S. SE/4 NE/4 SE/4 Sec. 17-23S-14W, Stafford County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.