

16-23-14W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Main Dock, Wichita, Kansas

Company- WESTGATE-GREENLAND OIL CO.-JACKSON DRILG. SEC. 16 T. 23 R. 14W
Farm- Grissman No. 1 NE NE SW

Total Depth. 4085 RB
Comm. 6-4-52 Comp. 7-3-52
Shot or Treated.
Contractor. Jackson Drilg. Corp.
Issued. 8-16-52

County Stafford
KANSAS



CASING:

8 5/8" 212' cem. w/225 sx
5 1/2" 4077' cem. w/150 sx

Elevation. 1960 DF

Production. I.P. 202 BO NW

Figures in parentheses Bottom of Formations.

sand	100
shale & shells	300
sand & shale	399
shale & shells	429
red bed & shale	870
anhydrite	905
shale & sand	1070
shale & shells	1730
shale & lime	1770
lime	1975
lime & shale	2315
shale & lime broken	2459
shale & lime	2860
lime	2990
lime & shale	3186
lime hrd	3228
lime	3420
lime & shale	3542
lime	3757
lime & shale	3842
chert	3894
chert, lime, shale	3917
lime & shale	3956
lime & chert	3969
shale	3980
sand	3994
shale & lime	4025
sandy lime	4030
arbuttle lime	4085 RTD
Total Depth	

DST: #5 3982-92' open 1
hr. 65' heavily oil & gas
cut mud, trace wtr in mud,
BHP 500#.

DST: #1, 3605-29' open 1 hr.
rec. 900# gas 60' oil & gas
cut mud, 510' muddy gassy oil-
trace of wtr. 90' salt wtr, 1370#
260# FP.

DST: #2 3657-71' open 1 hr. gas
to surface in 16 mins. rec. 390'
free oil 60' froggy oil, 1800#
BHP 140# FP.

DST: #3 3689-3717' open 1/4 hr.
gas in 2 mins. gauged 2,630,000
CF, 60' gas cut mud, IFP 720#,
FFP 1250#, BHP 1500#.

DST: #4 3725-41' open 1 hr. gas
in 10 mins. 450' free oil. 180'
froggy oil, IFP 100#, FFP 200#
BHP 1250#.

Tops:
Anhydrite 850
Heebner 3397
Brown Lime 3526
Lansing 3539
Base Kansas City 3779
Viola 3847
Simpson 3966
Arbuttle 4029