

16-23-14W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DEEP ROCK OIL CORPORATION
Farm- M. B. Beaver No. 1

SEC. 16 T. 23 R. 14W
NW SW SE

2310' W of EL, 990' N of SL

Total Depth. 4039

Comm. 7-26-54


Comp. 8-9-54

Shot or Treated.

Contractor. Gabbert-Jones Drilling Co.

Issued. 9-25-54

County Stafford
KANSAS



Elevation. 1951 DE

CASING:

10 3/4 @ 249' w/ 175 sx cmt.

Production. Dry

Figures Indicate Bottom of Formations.

sand & shale	190
shale & shells	250
shale, shells & sand	520
red bed	830
anhydrite	860
shale & shells	1365
shale, shells & lime	1705
lime & shale	2260
lime	2525
lime & shale	3105
lime	3854
lime & shale	3910
chert	3915
cherty lime	3960
lime	3977
Simspon sand	3994
shale	4024
lime	4039
Total Depth	

TOPS:

Heebner (Schl.)	3396
Brown lime	3529
Lansing	3542
Base KC	3783
Viola	3897
Simpson shale	3962
Simpson sand	3973
Arbuckle	4019

DST #1: 3660-82, open 45 min. SI 15 min. weak blow for 7 min. rec. 100' drlg. mud IFP O#, FFP O#, BHP 1100#

DST #2: 3979-94, open 1 hr, SI 20' min. immediate blow, light blow thruout, rec. 85' HO&GCM, SWC, FP O#, BHP 650#

Core Record: No. 1 3963-3994 Rec. 31'