

Company- JACKSON DRILG. CORP.
Farm- Miller No. 1

SEC. 23 T. 23 R. 14W
NE SE NW

23-23-14W

Total Depth. 4047

Comm. 12-6-51

Comp. 12-20-51


County Stafford

KANSAS

Shot or Treated.

Contractor. Jackson Drilg. Corp.

Issued. 1-19-52



CASING:

8 5/8" 260' cem. w/200 sx

Elevation. 1927 DF

Production. Dry

Figures Indicate Bottom of Formations.

soil & sand	50
sand w/shale	80
shale	295
sand	360
red bed w/shale & sand	833
anhydrite	857
shale & shells	1250
shale & shells w/salt	1265
shale w/salt	1300
shale & shells	1645
shale w/lime	1875
lime w/shale brks	1990
shale & lime	2970
lime	2980
shale & lime	3510
shale	3530
lime brown	3543
lansing lime	3782
shale & lime	3823
shaly congl.	3866
cherty congl.	3887
chert	3889
cherty lime	3917
lime, chert & shale	3937
chert & lime	3946
shale, lime & sand	3985
lime, shale & chert	4000
shale & sand	4035
arbuckle	4047 RTD
Total Depth	

Tops:

Heebner	3391
Brown Lime	3528
Lansing	3541
Base-Kansas City	3796
Congl.	3869
Viola	3894
Simpson	3975
Arbuckle	4027

DST: 3608-38', open 45 min.

rec. 75' muddy salt water,

BHP 1200#.

DST: 3675-3716, open 1 hr. rec.

310' slightly oil and gas cut

mud, no BHP.

DST: 3726-80', open 1 hr. rec.

2400' salt wtr, BHP 1270#.

Schlumberger ran.