

28-23-14W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company-GRINLAND DRILLING CO.
Farm- Chick Cadman No. 1

SEC. 28 T. 23 R. 14W
SE SE NE

Total Depth. 4110'
Comm. 10-29-53 Comp. 11-10-53
Shot or Treated.
Contractor.
Issued. 5-8-54

County Stafford
 KANSAS



Elevation. 1957' DE

Production. Pmp 7 B & some wtr.

Figures indicate Bottom of Formations.

sand w/clay	85
shale & shells	335
sand	385
red bed	865
shale, shells & sand	1250
shale, shells & salt	1690
lime & shale	3384
lime	3438
Heb. shale	3443
lime & shale	3474
shale & sand	3532
shale & lime	3573
lime	3823
shale & lime	3837
Conglomerate	3855
shale & lime	3909
chert	4010
chert lime & shale	4012
shale	4080
Arbuckle	4110 RTD
Total Depth	

Tops:	
Heebner	3438
Brown Lime	3573
Lansing	3583
Conglomerate	3912
Viola	3923
Simpson	4015
Arbuckle	4080

DRILL STEM TESTS:

#1 3710-17', open 1 hr, rec., 60' froggy
heavy oil 15' heavy oil cut mud, 1450#
BHP - gas to surface in 3 min.

#2 3762-3794, open 30 min., rec. 35' watery
mud - 1220# BHP.

Perf. 3763 - 3710' w/43 shots.