

28-23-14W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- PET. INC.
Farm- Cooper

No. 1

SEC. 28 T. 23 R. 14W
NE NW SE

Total Depth. 3830'
Comm. 11-16-63 Comp. 11-24-63
Shot or Treated.
Contractor. Garvey Drilling Co.
Issued. 2-8-64

County Stafford
KANSAS



Elevation. 1961' DF

Production. Dry

CASING:
8 5/8" 292' cem w/225 sx.

Figures Indicate Bottom of Formations.

clay & sand	185
gravel & redbed	292
redbed & shale	360
sand & gravel	420
shale & redbed	900
Anhydrite	920
shale & shells	1700
lime & shale	1930
lime	2030
lime & shale	2780
shale w/lime stks.	2945
shale & lime	3158
lime & shale	3581
Brown Lime	3595
lime	3830 RTD
Total Depth	

TOPS: SAMPLE	
Anhydrite	900
Base Anhydrite	922
Topeka	3042
Heebner	3442
Toronto	3460
Douglas	3483
Brown Lime	3580
Lansing	3591
Base Lansing	3812