

30-23-14W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- GREENLAND DRILLING CO.  
Farm- Cadman "A" No. 1

SEC. 30 T. 23 R. 14W  
NW SE NW

Total Depth. 4133'  
Comm. 4-4-60 Comp. 4-14-60  
Shot or Treated.  
Contractor.  
Issued. 5-28-60

County Stafford  
KANSAS



Elevation. 1991 RB

Production. Dry

CASING:  
8 5/8" 254'  
5 1/2" -----

Figures indicate Bottom of Formations.

sand	190
shale	254
shale & red bed	380
sand	430
red bed & shale	945
anhydrite	975
shale & lime	1080
shale w/lime strks.	1450
shale & lime	1750
lime & shale	1815
shale & lime	1840
lime	1955
lime & shale	2485
shale & lime	2690
lime & shale	3510
shale	3606
brown lime	3610
shale	3617
Lansing lime	3672
lime	3876
lime & shale	3941
lime	3998
lime & shale	4045
shale	4094
Arbuckle lime	4133RTD
Total Depth	

TOPS:	
Heebner	3472
Brown Lime	3606
Lansing	3618
Viola	3962
Simpson	4035
Arbuckle	4094