


32-23-14W

County Stafford
KANSAS

Total Depth. 4121
Comm. 11-19-51 Comp. 12-5-51
Shot or Treated.
Contractor. Jackson Drilg. Corp.
Issued. 1-12-52



CASING:

10 3/4" 252' cem. w/225 sx

Elevation. 1982 DF

Production. Dry

Figures Indicate Bottom of Formations.

clay & sand	40
sand	105
shale & sand	140
shale	250
shale & red bed	380
sand	430
sandy shale	550
shale & red bed	855
red bed	883
anhydrite	909
shale & shells	1320
shale w/salt strks	1390
shale & shells	1550
shale & lime	1865
lime	1970
lime & shale	2105
lime w/shale brks	2230
lime	2325
shale & lime	2900
shale	2925
shale & lime	3315
lime	3340
lime & shale	3450
lime	3512
shale & lime	3588
lime brown	3593
lime	3906
shale & lime	3925
congl.	3965
lime & chert	4024
chert	4027
simpson	4044
lime & shale w/chert	4075
lime w/shale & chert	4095
arbuckle	4121 RB
Total Depth	

Tops:

Heebner	3451
Brown Lime	3586
Lansing	3600
Viola	3960
Simpson	4024
Simpson Sand	4047
Arbuckle	4079

DST: 3658-93, open 1 hr.
rec. 945' gassy cut salt
water, 1250# BHP.

rec. 20' mud, no BHP.

DST: 3789-3811, open 1 hr.