

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


33.23-14W

Company- PALMER OIL CORP.
Farm- Gillmore No. 1

SEC. 33 T. 23 R. 14W
NE NE NW

Total Depth. 4104
Comm. 8-1-51 Comp. 8-15-51
Shot or Treated.
Contractor. Palmer Oil Corp.
Issued. 10-6-51

County Stafford
KANSAS



CASING:

8 5/8" 262' cem w/175 sxs.

Elevation. 1972 RB
1969(m)

Production. dry

Figures Indicate Bottom of Formations.

shale, shells	880
anhydrite	900
shale	1120
shale, shells	1856
lime, shale	2498
shale, shells	2603
broken lime, shale	2780
shale, shells	2932
lime, shale	3402
lime	3454
lime, shale	3497
shale	3576
lime, shale	3628
lime	3964
conglomerate	3998
cherty lime	4006
chert, lime	4060
lime	4065
shale, sand	4081
arbuckle lime	4104 RTD
Total depth	

Tops: RB	
Heebner	3457
Brown Lime	3597
Lansing	3612
Base K. C.	3862
Cherty Conglomerate	3964
Simpson sand	4036
Arbuckle	4081

DST 4030-4060 Tool open 30
minutes. Weak blow., rec.
15' very slight oil cut mud.
BHP 15#