

TRILOBITE
TESTING, INC.

RECEIVED
KANSAS CORPORATION

OCT 26 2007

CONSERVATION DIV.
WICHITA, KS

DRILL STEM TEST REPORT

Prepared For: **Oil Producers Inc of Kansas**

1710 Waterfront Parkway
Wichita KS 67206

ATTN: John Weir

14 23S 17W Pawnee KS

Wilson #2

Start Date: 2007.04.26 @ 09:31:59

End Date: 2007.04.26 @ 15:05:53

Job Ticket #: 28164 DST #: 1

15-145-21552
N2 NW SW
2310 FSL 4620 FEL

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Oil Producers Inc of Kansas

1710 Waterfront Parkway
Wichita KS 67206

ATTN: John Weir

Wilson #2

14 23S 17W Pawnee KS

Job Ticket: 28164

DST#: 1

Test Start: 2007.04.26 @ 09:31:59

GENERAL INFORMATION:

Formation: **Kind.Sd**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 12:09:24

Time Test Ended: 15:05:53

Test Type: Conventional Bottom Hole

Tester: Ray Schwager

Unit No: 28

Interval: **4110.00 ft (KB) To 4178.00 ft (KB) (TVD)**

Total Depth: 4178.00 ft (KB) (TVD)

Hole Diameter: 7.85 inches Hole Condition: Poor

Reference Elevations: 2085.00 ft (KB)

2080.00 ft (CF)

KB to GR/CF: 5.00 ft

Serial #: 6753

Inside

Press@RunDepth: 55.77 psig @ 4115.01 ft (KB)

Start Date: 2007.04.26

End Date:

2007.04.26

Start Time: 09:31:59

End Time:

15:05:53


Capacity: 7000.00 psig

Last Calib.: 2007.04.26

Time On Btm: 2007.04.26 @ 12:08:54

Time Off Btm: 2007.04.26 @ 13:11:24

TEST COMMENT: IFP Wk bl thru-out 1/2 " bl
Times 30 30 out



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2091.21	114.79	Initial Hydro-static
1	47.04	112.89	Open To Flow (1)
31	55.77	113.30	Shut-In(1)
62	93.33	113.99	End Shut-In(1)
63	1938.85	116.38	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
10.00	Mud	0.05

Gas Rates

Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Oil Producers Inc of Kansas

Wilson #2

1710 Waterfront Parkway
Wichita KS 67206

14 23S 17W Pawnee KS

Job Ticket: 28164

DST#: 1

ATTN: John Weir

Test Start: 2007.04.26 @ 09:31:59

Tool Information

Drill Pipe:	Length: 3858.00 ft	Diameter: 3.80 inches	Volume: 54.12 bbl	Tool Weight:	2200.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length: 240.00 ft	Diameter: 2.25 inches	Volume: 1.18 bbl	Weight to Pull Loose:	70000.00 lb
			<u>Total Volume: 55.30 bbl</u>	Tool Chased	0.00 ft
Drill Pipe Above KB:	9.00 ft			String Weight: Initial	56000.00 lb
Depth to Top Packer:	4110.00 ft			Final	56000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	68.02 ft				
Tool Length:	89.02 ft				
Number of Packers:	2	Diameter:	6.75 inches		

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			4090.00	
Shut In Tool	5.00			4095.00	
Hydraulic tool	5.00			4100.00	
Packer	5.00			4105.00	21.00 Bottom Of Top Packer
Packer	5.00			4110.00	
Stubb	1.00			4111.00	
Perforations	4.00			4115.00	
Recorder	0.01	6753	Inside	4115.01	
Blank Spacing	33.00			4148.01	
Recorder	0.01	13534	Outside	4148.02	
Perforations	27.00			4175.02	
Bullnose	3.00			4178.02	68.02 Bottom Packers & Anchor

Total Tool Length: 89.02



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Oil Producers Inc of Kansas

Wilson #2

1710 Waterfront Parkway
Wichita KS 67206

14 23S 17W Pawnee KS

Job Ticket: 28164

DST#: 1

ATTN: John Weir

Test Start: 2007.04.26 @ 09:31:59

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 48.00 sec/qt

Cushion Volume:

bbl

Water Loss: 10.38 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 7000.00 ppm

Filter Cake: 2.00 inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
10.00	Mud	0.049

Total Length: 10.00 ft

Total Volume: 0.049 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

DST Test Number: 1

14 23S17W Pawnee KS

Oil Producers Inc of Kansas

Inside

Serial #: 6753

Pressure vs. Time

