

UNION NATIONAL BANK BLDG WICHITA KANSAS

Plotted

Location Cen SW/4
1320' fr SL 1320' fr WL SW/4


Sec. 34 T.23 R. 17W.

Casing Record

County- Pawnee.

No. 1

20" 105 8 1/4" 4236 Farm- H. M. Millhouse
 15 1/8" 65/8" 4672 Company- Skelly Oil Co.
 12 1/8" 53/16" Contr.- Southern & Thurmond.
 Comm.- 4/20/1930. Comp.- 8/28/30.
 Total Depth 5002'. Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Elevation 4099

Figures Indicate Bottom of Formations.

Initial Production Dry.

Date Issued. 11/22/1930.

Formation	Depth	Formation	Depth	Formation	Depth
clay yellow	18	sdv lime lgt & some		shale drk & lime	4204
sand brown	27	shale	3020	brkn lime lgt	4220
clay yellow	30	brkn lime & black		shale red	4228
sand brown	40	shale	3060	shale gray & lime	4243
clay blue	65	brkn sdv shale lgt	3080	lime white	4245
sand brown	80	sdv lime gray	3090	brkn shale blue	
clay yellow	105	sdv lime brown	3100	& red	4280
shale red	400	lime drk hrd	3120	lime & chat Drlr's	
sand brown	600	lime lgt & brkn		log	4322
shale red	800	sand	3140	Had rainbow showing of	
shale red sft	1000	sdv lime drk hrd	3170	oil in Chert zone	4290-
brkn red shale	1100	lime drk hrd	3185	4297', reduced hole at	
shale red	1175	brkn lime & shale	3205	4297' and drld. ahead	
ssdy shale blue	1250	lime sand & shale	3225	without further showing.	
shale red	1350	lime white hrd	3232	chalky lime white	4360
shale gray & gyp		shale blue	3317	Had very lgt showing of	
shells	1400	sdv lime gray	3352	gas in chert zone at	4330'.
shale drk	1475	shale gray	3392	Straight-reamed hole	
shale gray & gyp		sand white	3410	4297-4360'	
shells	1600	sdv lime gray	3442	red rock	4370
shale blue & gyp		lime gray & shale	3462	Cave 4360-4370'	
shells	1725	sdv lime lgt	3484	sdv lime	4425
brkn blue shale	1775	lime gray	3530	red rock & lime	4435
shale gray & gyp		lime gray & sand	3555	lime	4440
shells	1800	sdv lime gray	3607	lime gray	4520
salt light	1895	lime lgt	3637	shale green	4590
brkn blue shale	1945	lime gray	3670	sdv lime gray	4605
sdv shale red	2000	lime brown	3687	1 BW PH 4590-4600'	
sticky shale blue	2025	lime lgt	3700	later increased & rose	
brkn gray shale	2075	brkn lime gray	3717	to 3000' in hole. Had	
sand gray & shale	2125	lime gray	3725	bad cave 4360-4605'.	
shale & gyp shells	2150	shale red	3732	Lost 25 days time at	
sdv lime white	2200	shale blue	3798	4605' fishing for lost	
lime gray & gyp	2250	lime drk	3800	bailer.	
shale gray & sand	2399	shale drk	3812	sand gray	4607
lime lgt hrd	2310	lime lgt	3824	shale drk	4611
sdv lime gray	2365	Top Lansing-Kansas City		lime lgt	4612
sdv shale lgt	2410	lime at 3816, from 3816-22,		lime white	4620
shale gray & lime		top 6' of lime was tight		lime gray	4628
shells	2460	fossiliferous lime with a		sand gray	4646
lime lgt	2480	few slight showings of oil		Steel line Correction-	
brkn lime & shale		& very little porosity.			4653
gray	2535	lime & drk shale	3836	lime gray	4655
lime lgt	2545	lime & shale gray	3850	shale blue	4668
brkn lime gray	2570	lime lgt	3880	lime gray	4812
lime gray	2580	shale drk	3898	UP & lowered 6 5/8" csg.	
shale blue & breaks		lime white	3950	to 4672' HFW in gray	
of red shale	2620	sdv lime brown lgt	3963	line 4680-4685'	
shale & red bed	2660	lime lgt	4000	sdv lime	4821
shale blue lgt	2720	shale drk	4018	lime gray	4880
shale blue	2765	lime drk with slate	4043	lime white	4927
lime gray	2780	sdv lime lgt & shale	4068	lime gray	4945
sticky gray shale	2800	lime lgt	4096	lime white	4963
shale black	2825	sdv lime gray	4110	lime gray	4980
shale blue	2875	shale blue	4160	lime white	4987
lime gray	2905	lime breaks with drk		white sand	4997
hale gray & lime		shale	4170	Steel line Correction	
hells	2935	shale brown & green &			4984'
ime gray	2950	red	4176	lime white	5002'
ckn lime lgt	3000	lime lgt	4180	Total Depth SIM	5002'