

8-23-17W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GEN. AMERICAN OIL OF TEXAS
Farm- L. J. Schartz No. 17

SEC. 8 T. 23 R.17W
SE SW NE
2820' N of SL, 3630' E of WL

Total Depth. 4990'
Comm. 1-5-58 Comp. 2-8-58
Shot or Treated.
Contractor. Hilton Drlg. & Pawnee Drlg.
Issued. 6-7-58

County Pawnee
KANSAS



Elevation. 2080' DF

Production. S W D W

CASING:

8 5/8" 308' cem w/225 sx.
5 1/2" 4508' cem w/1000 sx.

Figures Indicate Bottom of Formations.

sand	40
clay & shale	130
shale & shells	309
shale	365
red bed & sand	575
sand	645
red bed & shells	980
red bed & shale	1065
Anhydrite	1095
shale & shells	1530
shale, lime & salt	1870
shale & lime	2030
lime	2370
shale & lime	2445
lime	2530
shale & lime	3270
lime	3335
shale & lime	3420
lime	3635
shale & lime	3755
lime	4020
shale & lime	4162
shale, lime & chert	4225
chert	4260
chert, lime & sand	4315
chert	4355
lime, chert & shale	4431
lime & shale	4523
lime	4667
lime & chert	4730
lime	4869
lime & chert	4967
lime	4989 RTD
lime	4990
Total Depth	

TOPS:

Heebner	3628
Toronto	3646
Douglas	3656
Lansing	3731
Base Kansas City	4099
Marmaton	4123
Basal Penn.	4162
Mississippi chert	4202
Misner	4256
Viola Chert	4306
Viola Lime	4354
Simpson	4442
Arbuckle	4484

No DST were taken.
No Cores were taken.

Perforated 1 shot at 1790', would not circulate.
Perforated 4 shots at 1780', and cemented with 1100 sacks, cement did not circulate.
Perforated 1 shot at 350' and cemented with 129 sacks.