

820131

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 28 2007

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579CONSERVATION DIVISION
WICHITA, KSWELL LOG ----- ELAINE WHITE #1-35
Located: NW ~~NW~~ NE, Section 35-23S-17W, Pawnee County,
KansasOWNER: F. C. Holl, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling CompanyCOMMENCED: August 14, 1979
COMPLETED: August 21, 1979

TOTAL DEPTH: 4361'

<u>LOC</u>	
0 - 150	Sand and Clay
150 - 256	Shale
256 - 390	Red Beds and Shale
390 - 1113	Sand and Red Bed
1113 - 1132	Anhydrite
1132 - 1530	Shale
1530 - 2037	Shale and Lime Strs.
2037 - 4270	Lime and Shale
4270 - 4361	Chert and Lime

CASING RECORD

Ran 6 joints used 28#, 8 5/8" casing,
241.15' set at 253' K.B. with 225 sacks
60/40 Pozmix with 2% gel and 3% cc. Plug
down at 1:45 PM, 8-14-79.

Ran 99 joints new 10.5#, 4 1/2" casing,
4346.38' set at 4356' K.B. with 50 sacks
Howco Light and 100 sacks Pozmix with 18%
salt; 5# gilsonite, 1/8# flocele, 1/8#
tuffiber and 3/4 % CFR-2 per sack. 250
gal. mud flush and 20 bbl. salt flush ahead
of cement. Plug down at 12:45 AM, 8-21-79,
by Howco.

Deviation Surveys: 1/4° at 256'
1/2° at 2037'
1° at 4331'