

Himco Oil & Gas, Inc.
P.O. Box 2365, University Station
Enid, OK 73702-2365
Phone: (405)853-6199
Fax: (405)853-6960

Operator No: 32891

B & W Sales # 1
Pawnee County, KS
API 15-145-21460-0001

Frac Cherokee Sand @ 4,164' to 4,172' w/340 bbls water & 7500# 24/40 sand.
Swab back-had water

Perf upper Mississippi from 4,208' to 4,213' (4 holes per foot)

Acidize upper Mississippi w/500 gal 15% HcL acid-Swab back all water

Set CIBP @ 4,195' over Mississippi-start swabbing all water out of Cherokee

Set CIBP @ 4,000' over Cherokee Sand. Perf Kansas City from 3,891' to 3,895'
w/120 gal acid w/24 bbl flush. Swab back all water. TA