



PL

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Hinkle Oil Co., 1016 Union Center, Wichita, Kansas 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Gatterman Well No. 6

Sec. 27 T. 23 R. 18W Spot 165' FEL & 990' FSL

County Pawnee State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 337' with 225 sx. 3% CC 2% Gel

Production: 4 1/2" @ 4460' with 325 sx.

Type Well: Oil Well Total Depth 4500'

Drilling Commenced 2-1-84 Drilling Completed 2-11-84

Formation	From	To	Tops
Cellar	0	7	Anhydrite 1156
Sand, Shale, Clay	7	347	Lansing 3840
Shale, Lime	347	1174	Mississippi 4384
Shale	1174	1215	
Shale, Lime	1215	2936	
Lime	2936	3396	
Lime, Shale	3396	3580	
Lime	3580	3660	
Sand	3660	3690	
Lime	3690	3780	
Shale, Lime	3780	3840	
Lime	3840	3920	
Lime, Shale	3920	4035	
Lime	4035	4073	
Lime, Shale	4073	4240	
Shale, Lime	4240	4340	
Lime, Shale	4340	4384	
Lime	4384	4500	

FEB 28 1984

Approved Survey