


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

STANOLIND OIL & GAS CO.
James A. Boyd No. 1

SEC. 1 T. 23 R. 19 W
SW 1/4 SE
330' N SL 330' E WL SE 1/4

Total Depth: 5035'
Comm. 5-14-42 Comp. 6-16-42
Shot or Treated.
Contractor.
Issued: 7-11-42 Rotary O-5035

County. Edwards



CASING:
8 5/8" 621' 3" Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

cellar	9	Reworked Arbuckle 4931-71
surface clay	80	True Arbuckle dolomite 4971-5035
sand	95	
shale	165	
shale & shells	240	
sand	260	
shale & shells	365	
shale	500	
red bed	560	
sand	570	
shale blue	580	
red rock	643	
lime	650	
red bed	750	
sand	810	
red bed	1283	
anhydrite	1304	
red bed	1435	
shale	1870	
salt	2010	
shale	2095	
lime brkn	2545	
lime	2620	
lime brkn	2755	
lime	2815	
lime brkn	2955	
shale & shells	3030	
lime brkn & shale	3485	
shale	3500	
lime brkn	3565	
shale	3590	
lime	3600	
lime brkn	3695	
lime	3760	
lime brkn	3795	
lime sdy	3808	
shale	3875	
lime	4215	
shale	4250	
shale & lime	4285	
shale	4375	
lime	4408	
conglomerate	4428	
brkn lime & shale	4500	
chert	4503	
lime & chert	4519	
lime	4540	
shale & brkn sand	4575	
chert & sand	4583	
brkn lime & shale	4633	
lime	4637	
sdv conglomerate	4645	
lime brkn	4695	
lime	4705	
brkn chert & lime	4757	
lime	4780	
lime brkn	4845	
lime	4941	
reworked Arbuckle	4971	
Arbuckle	5035	
Total Depth.		