

Imperial's

STUECKEMANN #1 - C NE SE of Sec. 14-23S-19W,
Edwards County, Kansas

FO 3-5205

Ray Bacon-Mary Brown

(8 mi North 2 mi East Kinsley, Kansas)

8/15/69 - Call American
as have Overrid

8/8/69 Moving in over weekend.

8/11/69 Set 313' of 8 5/8" with 185 sacks cement.

Kelly Bushing 2236'

8/12/69 Drilling at 2775'

Base Anhydrite 1370' +866'

8/13/69 Drilling at 3180'

8/14/69 Drilling at 3610'

8/15/69 Charlie Shank, Geologist has gone out on Well--will call info.

Drilling at 3890'

Heebner 3862' -1626'

8/16/69 Drilling at 4092'

Toronto 3882' -1646'

8/17/69 Drilling at 4250'

Douglas Shale 3891'

8/18/69 Drilling at 4440'

Brown Lime 3962'

Expecting Cherokee Sand 4485'

Lansing K.C. 3972'

Base K.C. 4280'

Marmaton 4301'

8/19/69

Cherokee Sand 4493 -2257'

Mississippi 4525' -2289'

Took DST #1 in Cherokee from 4474' - 99' - open 1 hour had very
weak blow in 5 min. Recovered 10' mud.

ISIP 40#

IF 35#

FF 35#

FSIP 35#

Taking DST #2 in Mississippi 4522 - 47' now.

Will call report as soon as completed.

8/20 Mr. Bacon tried to call you last night--unable to reach you.

DST#2 from 4522 - 47' open 90 min. Recovered 680' Salt Water with few
specks of oil.

ISIP 1226#

IF 70#

FF 390#

FSIP 1169#

Ran Log - Had Zone in Lansing-K.C. and one in Cherokee.

Took DST #3 from 4099- 4127- (went back up to Lansing Kansas City)
open 30 min. Very Strong Blow. Recovered 1400' Salt Water

ISIP 1306#

IF 129#

FF 762#

FSIP 1306#

Running DST #4 in Cherokee from 4468' - 4514' -- don't expect to get
anything out of it.

over

		1	2	3	4	
1	8/21	Took DST #4 from 4468' - 4514' -- Packer failure.				1
2		Reran DST #4 from 4467' to 4516' - open 1 hour--recovered 495' Salt Water				2
3		ISIP	1329#			3
4		IF	46#			4
5		FF	293#			5
6		FSIP	1306#			6
7	<u>Total Depth 4547 or -2311'</u>					7
8	Plugging this morning.					8
9						9
10						10
11						11
12						12
13						13
14						14
15						15
16						16
17						17
18						18
19						19
20						20
21						21
22						22
23						23
24						24
25						25
26						26
27						27
28						28
29						29
30						30
31						31
32						32
33						33
34						34
35						35
36						36
37						37
38						38
39						39
40						40