

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

3-23-21W

COMPANY J. M. HUBER

SEC. 3 T. 23 R. 21W

FARM Kingry

NO. 1

LOC. C SE SE

TOTAL DEPTH 4597'

COMM. 11-8-63

COMP. 11-21-63


SHOT OR TREATED

CONTRACTOR Murfin Drlg.

ISSUED 9-3-66

COUNTY Hodgeman

KANSAS



CASING

20	10	
15	8	5/8" 244' cem w/ 200 sx
12	6	
13	5	
		4" 4598' cem w/ 150 sx

ELEVATION 2341' RB

PRODUCTION 54 BOPD, NW, GR
 31.5; (Miss 4591-98)

FIGURES INDICATE BOTTOM OF FORMATIONS

40' Post Rock
 244' Shale
 900' Shale and Red Bed
 1030' Sand
 1445' Shale
 1475' Anhydrite
 1530' Shale
 1830' Shale and Shells
 2545' Shale and Lime
 2650' Lime and Shale
 2700' Lime
 2955' Lime and Shale
 3035' shale and Lime
 3345' Lime and Shale
 3440' Shale and Lime
 3580' Lime
 3765' Lime and Shale
 4317' Lime
 4408' Lime and Shale
 4498' Lime
 4565' Lime and Shale
 4585' Chert and Mississippi
 4595' Chert
 4595' Rotary Total Depth
 4597' No Log
 Total Depth

Marmaton	4368
Cherokee	4462
Cherokee pay	4502
Mississippi Osage	4574

TOPS: SCOUT
 Stone Corral (smp) 1437
 Well (smp) 1892
 Wabaunsee (smp) 3338
 Heebner 3915
 Lansing Kansas City 4000
 Drum State of Kansas 4144

County of Sedgwick

I, Robert Buford, of the State of Kansas, County of Sedgwick, do hereby certify that the above is a true and correct copy of the original log and sample data as filed in the files of the Kansas Geological Society.