

3-23-21W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **J. M. HUBER CORPORATION**

SEC. 3- T. 23 R. 21W

FARM **Kingry**

NO. 2

LOC. C SW SE

TOTAL DEPTH **4567'**

COMM. **1-20-64**

COMP. **2-4-64**


SHOT OR TREATED

CONTRACTOR **Gabbert-Jones**

ISSUED **8-6-66**

COUNTY **Hodgeman**

KANSAS



CASING

20	10	
15	8 5/8" 239'	cem w/ 200 sx
12	6	
13	5 1/2" 4557'	cem w/ 150 sx

ELEVATION **2311' KB**

PRODUCTION **65 BOPD, NW, GR 35.5**
(Miss Osage 4543-57)

FIGURES INDICATE BOTTOM OF FORMATIONS.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	50	SURFACE CLAY	
50	239	SHALE & SHELLS	RAN 7 JOINTS 8 5/8" CASING SET @ 239' @/200 BAGS CEMENT
239	895	SHALE & RED BED	
895	990	SAND	
990	1005	RED BED	
1005	1411	RED BED & SHALE	
1411	1440	ANHYDRITE	TOPS: SMP
1440	1650	SHALE & SHELLS	Stone Corral 1411
1650	2405	SHALE & LIME	Base Stone Corral 1424
2405	2548	LIME	Wabunsee 3307
2548	2630	LIME & SHALE	Base Heebner 3880
2630	2690	LIME	Lansing 3966
2690	2880	LIME & SHALE	Marmaton 4331
2880	2962	LIME	Mississippi Osage 4541
2962	3555	SHALE & LIME	
3555	3675	LIME	
3675	3895	SHALE & LIME	
3895	4217	LIME	
4217	4271	LIME & SHALE	
4271	4543	LIME	
4543	4546	LIME, SHALE & CHERT	
4546	4567	CORE	
4567	TL		RAN 140 JOINTS 5 1/2" CASING SET @ 4557' @/150 BAGS CEMENT

I, **E. E. HALL**, CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN THE C SW SE SECTION 3-23-21W, KINGMAN COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)