

State Geological Survey
WICHITA, BRANCH
KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

AUG 23 21W


API No. 15 — 083 — 20,319
County Number

S. 6 T. 23 R. 21^{NE} W

Loc. C NW SW

County Hodgeman

640 Acres
N



Locate well correctly

Elev.: Gr. 2341

DF 2343 KB 2346

Operator

Donald C. Slawson

Address 408 One-Twenty Building
Wichita, Kansas 67202

Well No.

#1

Lease Name

Bauer "D"

Footage Location

North

West

660

feet from (N) (S) line

660

feet from (E) (W) line

Principal Contractor

Slawson Drilling Company, Inc.

Geologist

Ralph Ruwwe

Spud Date

August 24, 1973

Total Depth

4673

P.B.T.D.

Date Completed

September 1, 1973

Oil Purchaser

N/A

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		342	60/40 Poz	250	3% HA5

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Donald C. Slawson		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name BAuer 'D'		Dry Hole
S <u>6</u> T <u>23S</u> R <u>21</u> ^{WE} _W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
			No log run.
Surface Hole	0	345	
Shale & Shells	345	800	
Blaine Lime	843	857	
Shale	857	950	
Sand	950	10 60	
Shale	1060	1473	
Anhydrite	1473	1511	
Shale & lm	1511	1560	
Shale & shells	1560	1992	
Lime & Shale	1992	4015	
Lime	4015	4153	
Lime & Shale	4153	4298	
Lime	4298	4441	
Lime & Shale	4441	4491	
Lime	4491	4607	
Miss	4607	4673	
DST #1 4568-4607, 30-30-30-30, rec 20' M, NS IFP 26-35#, IBHP 89#, FFP 35-35#, FBHP 53#			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
123456789101112 RECEIVED STATE GEOLOGICAL SURVEY OF KANSAS	 James C. Remsberg Petroleum Engineer September 11, 1973		